

I-64 Sherman Minton Bridge Inspection, Closure, & Structure Retrofit



Background

Figure 1. Bridge and major elements identified.



Background

- The bridge carries approximately 70,000 vehicles per day on I-64 over the Ohio River.
- Consists of two 800 foot simple span tied arches.
- There are two decks. The lower deck carries traffic into Kentucky while the upper deck carries traffic to Indiana.



Background



Background

- Designed in 1959
- First Deck opened in 1961
- Second deck opened in 1962
- 100 ksi




Why was there concern?




Type of Construction

- Tied arches are FRACTURE CRITICAL bridges.
- Failure of the tie = likely collapse of the entire span




Material Properties

- Type of Material
 - "T1" Steel
 - VERY high strength steel
 - Susceptible to FRACTURE at cold temperatures and with small cracks
 - Fractures are cracks that propagate through the steel at rates faster than the speed of sound
 - Hydrogen induced cracks may form during welding




Type of Construction




- Think of a bow (like in a bow and arrow....)
 - Stand it on a table like shown
 - Push down on the bow
 - What would happen if we cut the string?

Slide courtesy of Baker



Sensitive Details

- Sensitive Details
 - Tie girder welds
 - Diaphragm plates
 - Lateral bracing details
 - Some longitudinal fillet welds




Type of Construction

Source: 1978 FHWA Technical Advisory

- ...the *serious consequences of weld cracking associated with the tie girder of a tied arch structure should not be overlooked.*
- ...it is one of the most nonredundant structures, relying entirely on the capability of two tie girders to accommodate the total thrust imposed by the arch ribs

Slide courtesy of Baker



Sensitive Details


Tie Girder Welds



Slide courtesy of Baker

Sensitive Details


Tie Girder Welds



Slide courtesy of Baker

Sensitive Details

Diaphragm Lugs




33 diaphragms per tie x 2 ties x 2 spans x 8 lugs per diaphragm x 2 legs = 2112 welds

Slide courtesy of Baker

Sensitive Details

Tie Girder Welds




176 Individual welds per tie x 2 ties x 2 spans = 704 potential fracture sites

Slide courtesy of Baker

Sensitive Details


Lateral Bracing Plates



Slide courtesy of Baker

Sensitive Details

Diaphragm Lugs



Slide courtesy of Baker

Sensitive Details

Lateral Bracing Plates



Slide courtesy of Baker

Sensitive Details

Lateral Bracing Plates
11 panels x 2 plates per panel x 2 ties x 2 spans = 88 connection plates

Slide courtesy of Baker

Inspection

- Material samples
- Fracture Mechanics analysis
- Inspectors were proof tested
 - NDT
 - Vision

Small logo in the bottom left corner.

Inspection

Inspection

Small logo in the bottom left corner.

Inspection

Small logo in the bottom left corner.

Inspection

- Comprehensive Inspection Plan Developed
 - Visual Inspections
 - Instrumentation
 - NDT
 - Magnetic Particle
 - Ultrasound
 - High Intensity X-ray
 - Radiography

Small logo in the bottom left corner.

FHWA Technical Advisories


- 5140-32
 - Inspection of Fracture Critical Bridges Fabricated from AASHTO M270 Grade 100 (ASTM A514/A517) Steel

Small logo in the bottom left corner.

Retrofit # 1

Why was the bridge closed?

- ## Retrofit #1
- Remove diaphragm lugs & inspect
 - Retrofit lateral bracing connections & inspect
 - Core or install dog-bone detail based on results from inspection and fracture mechanics model



Why was the bridge closed?



Retrofit # 2



Metro Area Map



Retrofit #2

Timeline

- Bridge was closed September 9, 2011
- Repair plan announced September 30, 2011
- Contract let October 19, 2011



Traffic Mitigation

- Detour
- Signal retiming
- Add temporary lanes on Interstate ramps
- US 31 bridge: reversible lane
- Extra Hoosier Helper service patrols
- Message boards
- Other



Retrofit #2

Short Listed ideas


- Local Plating
- Global Plating
- Post-tensioning
- Replacing the Tie




Retrofit #2

Considerations


- Location of indications
- Future Inspection
- Availability of steel
- Length of Construction



Retrofit #2




Global Plating Option – Odd Joint



Retrofit #2

- Chosen Solution
 - Global Plating
 - Installation of dog-bones to isolate the welds in the top and bottom plate of the tie-girder




Retrofit #2




Global Plating Option



Retrofit #2



Global Plating Option – Even Joint



Retrofit # 2



Top Plate: Dog Bone - Crack Isolation





Bidding Results

Contractor	Part A	Closure Days	Total
Hall Contracting	\$13.9M	135	\$27.4M
Walsh Construction	\$17.2M	150	\$35.2M
American Bridge	\$16.4M	195	\$35.9M

- ### A + B Bidding
- **Contract was bid in 2 parts**
 - **Part A** – Includes all pay items in the Schedule of Pay Items
 - **Part B** – Total dollar value of closure days at \$100,000 per day
-

- ### Moving at the Speed of Business
- Bridge Closure – September 9, 2011
 - Mandatory Pre-Bid – September 27, 2011
 - Contract Letting – October 18, 2011
 - Pre-Construction Conference – October 19, 2011
 - First Chargeable Closure Day – October 19, 2011
-
-

- ### A + B Bidding
- **The Great Motivator**
 - \$100,000 per day incentive for beating closure days bid
 - \$100,000 per day penalty for not meeting closure days bid
-
-

- ### Major Project Quantities
- 2.4 M pounds of structural steel
 - Just over 1,000 steel plates
 - Plates up to 67' in length
-
-

Major Project Quantities

- 55,000 field drilled holes
- 73,000 bolts



Structural Steel Placement



First Steel Arrived December 19, 2011




Field Drilled Holes for Bolts



Structural Steel Placement



Structural Steel - Bolting



Steel Placement

- Repeat the process 1,000 times




Bridge Opening 2/17/2012




Sherman Minton Bridge




~~September 17, 2011~~
September 17, 2012




Thank you to:

- Baker
- FHWA
- KYTC
- Robert Connor and Purdue University
- Phil Fish and Associates
- ATS
- Thornton Thomasetti
- Glenn Washer



Sherman Minton Bridge

- Hall bid 135 closure days (Part "B" of bid)
- Bridge reopened on day 122
- 13 days x \$100,000 = \$1.3M incentive



Questions?

Anne Rearick
Director of Bridges
(317)232-5152
arearick@indot.in.gov

